

Diagram No. 1222-4

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

Type of Survey Wire Drag

R/H-20-2-69

Office No. FE-233 WD

LOCALITY

State Virginia

General Locality Chesapeake Bay

Locality Off Little Creek and

Cape Henry

1969

CHIEF OF PARTY

LCDR C. Andreasen

LIBRARY & ARCHIVES


DATE August 26, 1983

☆U.S. GOV. PRINTING OFFICE: 1980-766-230

Chts - 12254 - 12256 - 12221 - 12220 - 12205 se

TO SIGN OFF SEE
"RECORD OF APPLICATION"

NOAA FORM 77-28 U.S. DEPARTMENT OF COMMERCE (11-72) NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	REGISTER NO.					
HYDROGRAPHIC TITLE SHEET						
2	FE - 233 WD					
INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form,	FIELD NO.					
filled in as completely as possible, when the sheet is forwarded to the Office.	R/H-20-2-69					
State Virginia						
General locality Chesapeake Bay						
Locality Off Little Creek and Cape Henry						
Scale 1:20,000 Date of surv	rey Oct. 24 - Nov. 26, 1969					
Ostructions dated Oct. 8, 1969 Project No.						
Vessel NOAA Ships RUDE & HECK and Launches HE-1						
	, 1,0-1, 1,0-0,					
Chief of party LCDR Christian Andreasen						
Surveyed by LT Merritt Walter, ENS Pressley Camp	bell, & ENS Joseph Morley					
Soundings taken by Weith O'S o'And Me and Me						
Graphic record scaled by N/A						
Graphic record checked by N/A						
Protracted by M. B. Hickson Automat	red plot by N/A					
Werification by M. B. Hickson						
fective Depths						
Soundings in fathoms feet at MLW MLXWXX						
REMARKS: All times are recorded in local time	(075° Meridian).					
1111015 / SURF	MSM 6/11/85					
	110111 011110					



U.S.C.& G.S.S. RUDE & HECK

LCDR.C. ANDREASEN, CHIEF OF PARTY

PROGRESS SKETCH

SCALE 1:80,000

1969

OCT. NOV.

626

Descriptive Report

to

Accompany

Wire Drag Investigation

Project AMC-SP-5-69

Little Creek, Virginia

1969

LCDR Christian Andreasen - Chief of Party

A. Authority

The authority for this survey is contained in Project Instructions AMC-SP-5-69, Little Creek, Virginia, dated 8 October 1969.

B. Character & Limits of the Work

The area surveyed is in the Chesapeake Bay between Little Creek and Cape Henry, Virginia, and consisted of two items: an obstruction plotted at 36°55.8'N, 76°09.5'W and a wreck (PD) plotted at 36°57.3'N, 76°04.05'W.

C. Control and Shoreline - See section 2. of the Verification Report

The investigation was carried out on the largest scale chart of the area, C&GS 481, 1:20,000 scale. All control was $\sqrt{}$ visual in accordance with publication 20-1 requirements, using charted triangulation objects.

D. Date of Survey

The survey commenced on 24 October and terminated 26 November 1969.

E. Tide Reducers - Smooth tides have been applied to the smooth sheets (AfD).

All soundings and effective depths are in feet at Mean Low Water using predicted tides. See tide note. All least depth soundings were accomplished with divers and hand leads.

1.

E. Tide Reducers (Cont'd.)

All soundings, effective depths used in this report and on the preliminary area and depth sheet are in feet at Mean Low Water using predicted tides. Because of the time delay between our field work and the arrival of smooth tides, processing with smooth tides could not be accomplished prior to our 1970 sailing. No predicted tides were entered in the volumes. Smooth tides need to be entered and processed. Smooth tides were entered processed during verification.

F. Junctions - See section 3. of the Verification Report.

Items investigated formed no junctions with other surveys.

G. Splits

The wreck (PD) plotted at 36°57.30N, 76°04.51W was not dragged to completion due to termination of field work for the season under direction from AMC. - See section 5. of the Verification Report (V.R., Pg.4 Section 5.0.2)

The obstruction plotted at 36°55.81N, 76°09.54W is considered to have been wire dragged over a sufficient area with no splits remaining. - See section 5. of the Verification Report Section 5.1).e)
Hung at 15' and cleared by 14' at lat.36'55.80' y long. 76'09.48' w delete charted information and chart an obstruction cleared by 14ft. in the location shown on the present survey.

2.

626

H. GROUNDING & SHOALS

DAY	Lates Tana		Cleared	Least
DAY	Lat & Long		Depth	Depth
/1. a day 27 Oct. 69	36°56'02"N 76°10'12"W	N buoy aground fix #3-#9	17-19' V	Service Special
4 corners	36°55'57''N 76°10'09''W	#1 buoy aground fix #4-#9	19	roundings not in offict with s
	36°55'55"N 76°10'04"W	#2 buoy aground #5-#9		arted depths.
	36°55'57"N 76°09'58"W	(buoys set too deep)		
√2. a day	36°55 '54" N	HANG (buoys grounded - Do not	(see V.P. Item	5.a.1),c) I to E
27 Oct. 69	76°10 104 W		15'16" from 1	
	36°55 '52" N	@17'-same hang as strip V-1		16/2
V3. a day		HANG (wire cable-150)	15' from Wto	E removed,
27 Oct. 69	76°09 1361 W	recovered from bottom)	15' from E to	w do not
√4. b day		HANG - temp. between buoy		Chart
3 Nov. 69	36° 55,88' 76° 10.14'	#3-#4 (investigation proved	14' from Wto	E Do not
	16 10:17	fish net hung in wire)	7' fram Ets	w chart
√5. b day	36°55148"N	N buoy aground fix #4-#5	14-15	
3 Nov. 69	76°08'46"W	(buoy set too doon)		
	36°55'47"N	D TOWNS	ing not in compand depths.	Cictwith
~	76°0813911W	Critic	и аврть.	
1	7	@ 34' (SeeV.R.se	ction4.b.36P	5, item al)
4 Nov. 69	36°57 '40" N	HANG - hang was a wreck	Not Clearer) Sinvast. F
4 Nov. 69 11 150	76°05 -14- W	previously wire dragged to	/	NO L.D.
	5	32! our drag eff. depth was 3! hang is not the obstr. Located by fart	- Hang not	investigated - this
	approx.	(0.38' (estimated)	no. on 21-7/77	WD see the
7. e day (1) 13 Nov. 69 (1)	36°5/ 13" N	HANG - temp. drag parted	1\38' from E to	W Section 4 Digit
13 NOV. 69 6	16 03 18 W	HANG - temp. drag parted (see paragraph "K" in paragraph tang not investigated	K)36 from W to E	
8. e day	36°57 102"N	HANG - charted depth 39140		
13 Nov. 69	76°03+42+W	eff. depth 39 (hang caused	35 from E	to W only
	.70′	by buoy grounded)	1.0	
,/9. f day	36°56128"N	HANG (see paragraph "K")- No hang	23 (D day) from W to E
14 Nov. 69	76°09+50+W	was noted for strip F-1, only that the draparted after pos#8. There is no indication in any of the survey records of a hang on this	g 201 from I	to W
√10. f day	36°55'52"N	#1 Buoy grounded fix #31-#32	151 from W	to E /
14 Nov. 69	76°09'34"W	(buoy set too deep)-ships	/13 from E	to W
4 corners	36°55'48"N	unable to mill off	15	
	76°09'38"W	Grounding,	not in conflict i	with charted depths
	36°55'49"N			
	76°09'25"W			
	36°55'46"N			
	76°09'29"W			

H. GROUNDING & SHOALS (CONTID.)

Cleared Least Depth Depth Day @ 15'- possible hong on bottom 11. g day \$36°55147"N 17 Nov. 69 76°09127"W HANG - Charted depth 13. 131 in both directions 14 from W to E V eff. depth 13. (sag, buoy grounded) V@ 16 (estimated) - same hang as strip A-2 19+ 15' from Who E On not 15' from EtoW Hang HANG-(buoy weight slipped, 36°55 + 55"N 12. j day 76°09"27"W 19 Nov. 69 buoy set at 16'. Cleared depth 19') @ 19' 21.8 OK 13. 1 day 200 76°55 56"N 25 Nov. 69 76°09 04"W HANG - Pinnacle rock (see paragraph "K") tem #2.) 19' from W to E \$V.R. pg 6, I tem # 14) See Evaluator's Report (see paragraph "K") tem #2.) L day 36 56.52' Temp. Hang @ 22' - Navy divers found 21'- from E to W only the hong to be cargo lost during transfer between ships . Temp. Uninvestigated Hange 19" 18' from E to W 13' from W to E Note: All depths contained in this section are based on predicted tides. All depths have been corrected for smooth tides. V (approx.) 36° 56.17' 76° 09.90' Grounding of buoys N&1 at pos# 2 at a depth of 22' - charted depths are 25' - see section 5. of the J day 21 from W to E only Do not chart. See V.R. section 5,a.l., h Varification Report. Do

I. General Notes

See Paragraph "K".

J. Currents

Currents run along shore and change as predicted in the current tables.

Drag experience showed an apparent tendency for the bottom current to shift approximately 30 minutes to 1 hour after the surface currents. The surface currents followed the tables very well.

K. Discrepancies and Comparison with Previous Survey & Charts - See sections 4 \$5.

The findings of this survey have been compared with C&GS Chart 481.

- 1. At latitude 36°56.5 N, longitude 76°09.8 W, an obstruction was located extending two feet off the bottom. The item was buoyed and the Navy notified. Navy divers intended to raise the obstruction after identifying it as a piece of cargo lost during transfer between ships in the area. Later consultation with the Navy revealed that they had lost the buoyed location of the object, and further attempts to recover it would not be made. It is recommended that the chart show an obstruction at this location with a depth of 23.0 feet. Concur real tides to see section 8. of the Verification of the Verification at the Verification of the Verification at the verification of the Verification of the Verification at the verification of the Verification of the Verification of the Verification at the verification of the Verification of the Verification of the Verification at the verification of the Verification of the Verification of the Verification of the Verification at the verification of the Verificat
- 2. At latitude 36°55.9 N and longitude 76°09.1 W, an obstruction report.

 was located with a diver-verified least depth of 21.8 feet. The obstruction was irregular in shape, but had an overall size of approximately than it is distance above the bottom was 5.4 feet. It should be as a rect noted that charted depths in this area are 22 feet. A depression or the volume vestigated. Since the obstruction exists, the limits of which were not in-the volume vestigated. Since the obstruction does not extend above the general pg4, item f. bottom, it is recommended that this obstruction not be charted. Section so the

L. Personnel and Equipment

H-9255 WD (1971-72)

The following color scheme was used for towing vessels: describes this as a concrete

RUDE ASV 90 - Blue
HECK ASV 91 - Red
RU-3 20' Bertram - Purple
EX-3 25' Bertram - Green

Additionally launches HE-1 & RU-1 were used for towing vessels.

The party was organized as follows:

LCDR Christian Andreasen - Chief of Party CO Ships RUDE & HECK
Officer in Charge of Ship HECK or RU-3

LT Merritt Walter - XO Ships RUDE & HECK

Officer in Charge of Ship RUDE or EX-3

ENS Pressley Campbell
ENS Joseph Morley

- Operations Officer
- Administration Officer

626

Field Works Officer

* Disregard recommendation on item #2. This item is usuperseded

by H19265 WD (1971-72), Chart a submobstralegred to 1764. 9255 WD

5. (1971-72)

M. Miscellaneous

None

N. Recommendations

item #1

The obstruction, a concrete clump, plotted at latitude 36°55.8'N, See section G, longitude 76°09.5'W was not located. Sea & Ship propellor action paragraph 2 in this from the numerous amphibious landings at this point have in all D.R. & V.R. sections probability made this item undistinguishable from the bottom, no 5.,a.1), & 5.a.1) e longer presenting a hazzard to navigators. Note: Presurvey review showed this obstruction to be a 3' x 3' concrete block. It is felt that sufficient wire drag has been accomplished to prove that the item presents no danger to navigation. It is recommended that this item be removed from the chart. Do not concur — see section 5. For the Verification Report.

The wreck plotted at latitude 36°57.3'N, longitude 76°04.05'W, in anchorage area LA-3 was not dragged to completion. Each drag strip through the area had excessive lift on the same section on different days, while passing over a particular area, as if the drag was sliding over an obstruction without hanging. Additional work is required under future instructions in order to prove or disprove this item. - Concur - see section 8. of the Verification Report.

O. Statistics

DATE	DAY LETTER	VOL.	NAUTICAL MILES	NO. OF POSITIONS	TENDER SOUNDINGS	TENDER POSITIONS
27 Oct	a	I	1.0	38	2	2
3 Nov	b	1	1.7	32	1	1
4 Nov	С	II	2.9	70	1	1
7 Nov	d	II	1.7	42		
13 Nov	e	11	2.7	44	2	2
14 Nov	£	I	3.9	64	1	1
17 Nov	8	I	1.7	48	ī	ī
18 Nov	ĥ	I	1.6	20	,	_
19 Nov	i	III	0.8	12	1	1
24 Nov	k	11	1.7	26		_
25 Nov	1	11	1.7	38	1	1
26 Nov	m	IV	1.9	34		
Totals	12	4	23.3	468	10	10

Area 2.0 square nautical miles

APPROVAL SHEET

The attached report, records, and plotting sheets have been inspected by me and are approved.

Commanding

USC&GSS RUDE & HECK

Note: To date, smooth processing of records is incomplete and all recommendations contained herein are based on Predicted Tides. Records are being forwarded to the Atlantic Marine Center, as per their instructions, for final processing.

Smooth work remaining:

Enter smooth tides

Draw smooth effective depth diagrams

Smooth sheet

Smooth Area and Depth sheet

Accomplished

during processing Smooth Area and Depth sheet

NAME	SOURCE		
ABE	Cape Henry Lighthouse (New)	G 1550 1943	
CAM	Cape Henry, Weather Bureau, Signal Mast	G 4267 1939	
EVA	Casemate (Use)	G 4267 1939	
IDA	Chesapeake Beach Tower A (Use)	G 4267 1939	
JET	Little Creek	G 4267 1944	
LAY	Little Creek, NAB Radar Reflector	G10989 1955	
MET	Little Creek, NAB Desert Cove Water Tank	G10989 1955	
RAD	Radio Transmitting Tower	6 5694 1941	
SOX	Rude & Heck established hydro signal Thimble Shoal Tunnel South Light, 1968	Volume I; guide vessel	
TUB	4th order triangulation — Labeled as R/H Hydrographic station since no data for this station could be found.	AMC Operations	

Control Listing FE-233 WD

Station Number	Station Name	Latitude	Longitude
001	CAPE HENRY LIGHTHOUSE, 1887	36° 55′ 34, 335"	
	CAPE HENRY WEATHER BUR MAST, 1939	36° 55′ 46.556″	76° 00′ 42, 177″
003	CASEMATE USE, 1939	36° 55′ 49.493″	76° 01′ 53, 280″
004	CHESAPEAKE BEACH TOWER A USE, 1939	36° 55′ 09.623″	76° 08' 06.323"
005	LITTLE CREEK, 1929	36° 55′ 57.125″	76° 10′ 35.961"
006	LITTLE CREEK, NAB RADAR REFLECT, 1955	36° 55′ 21,634″	76° 08' 30.694"
007	LITTLE CREEK, NAB DESERT COV TK, 1955	36 55' 14.382"	76° 09' 42.063"
008	ZADIO TRANSMITTING TOWER, 1941	36° 55' 48.926"	76° 12′ 18.828″
009	THIMBLE SHL TUNL 5 LT, 1968	36° 51′ 59.363″	76° 06′ 45. 986″
010	R/H HYDROGRAPHIC STATION	36 58' 50.800"	76° 06′ 24.000″
011	LITTLE CREEK AMPHIB BASE TK, 1952	36° 55′ 06.190"	
012	LITTLE CREEK NAV AMPH BASE TK, 1952	36°54′ 31,740″	

The source of station 009 is the FFRIDS Listing for OPR-DIOS.

No G.P. could be found for station 010 which was noted as being 4th order triangulation. The listed G.P. was scaled from the bootsheets. 626

All other listed control stations are published N.G.S. control.

TIDAL NOTE

Hourly tide heights were supplied by the Washington Office (Chief, Tidal Section C-3312) as observed at Hampton Roads (Sewells Pt.), Virginia, Standard Tide Gage (75th Time Meridian).

The following corrections were applied to the indicated investigations:

- For the Minnie "V" in Naval Anchorage L-A, 1^h 04^m substracted from hourly data.
- For investigation in Amphibious Anchorage L-E, 0^h 54^m substracted from hourly data.

See the Approved Tide Note.

DATE: May 11, 1982

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SURVEY

TIDE NOTE FOR HYDROGRAPHIC SHEET

Processing Division: Atlantic Marine Center:

Hourly heights are approved for

Tide Station Used (NOAA Form 77-12): 863-8610 Hampton Roads, Virginia

Period: October 1 - November 30, 1969

HYDROGRAPHIC SHEET: 20-2-69

OPR: AMC SP-5-69

Locality: Chesapeake Bay, Virginia

Plane of reference (mean XXXXXXXXXXX low water): 3.9 feet

Height of Mean High Water above Plane of Reference is 2.5 feet

REMARKS: Recommended Zoning,

For Item #1, at GP 36°56.00' latitude, 76°09.00' longitude and Item #2 at GP 36°57.00' latitude, 76°04.00' longitude, zone on 863-8610, Hampton Roads, Virginia and apply -1 hour time correction and x1.06 range ratio.

Chief, Tidal Datums and Information Branch

NOAA FORM 76	-40					TIONAL OC			MENT OF COMMERCE	ORIGINATING	ACTIVITY
(8-74)		NONE	OATING A	IDS OR LAN				AIMOSPHE	RIC ADMINISTRATION	HYDROGRAPHIC	
Replaces C&GS	Form 567.	NONFI	LUATING A	IDS OK LAN	DMAKKS	FOR CIT	AKIS			GEODETIC PART	
TO BE CHA	RTED	REPORTING UNIT	Office	STATE		LOCALITY			DATE	COMPILATION AC	TIVITY
TO BE REV		Processing Divisio	m			Chesap	peake B	ay		QUALITY CONTROL & REVIEW GRP.	
TO BE DEL	ETED	Atlantic Marine		Virginia		Off Litt	He Creek	& Cape He	my 7-1-82	COAST PILOT BRANCH	
The following	objects l	HAVE HAVE NO	T been ins	pected from se	award to de					(See reverse for respo	nsible personnel)
OPR PROJECT		JOB NUMBER	SURVEY		DATUM						
						N.A. 192	7		METHOD AND DAT	E OF LOCATION	
AMC-SP-5-	69		FE-2.	33 WD		POSI	A SHIRLD THE RESERVE TO		(See instructions		CHARTS
	1				LATI	TUDE	LONG	ITUDE			AFFECTED
CHARTING	Record re	DESCRI eason for deletion of lan		navigation.		"		111	OFFICE	FIELD	
NAME		angulation station names			0 /	D.M. Meters	0 /	D.P. Meters		A to the second of	
	1	11- 1: 1+			1	1	,		Published		12254
	cape	Henry Light			-101	34.335		27. 216			12254
	1 con	r 1/2 104 1.04		207)	36 55	34.335	76° 00'		Triangulation Data		(481)
-	LLAP	E HENRY LIGHT	THOUSE, I	101/	A STATE OF THE STA		2 2 2 2				100-1
	Little	Creek Harbor	Vetry Light			57.125		35.961	Published .		12254
	111	4/5 405-1	450)		36° 55'		76° 10'		Triangulation		(481)
	(417)	HE CREEK, 19	929)	<u> </u>					Triangulation Data Published in		
						59,363	,	45.986	Published in		12254
	1 himb	le Shoal Tunne	el-South L	ight	36°57'		76° 06		FFAIDS Listing		(441)
				0		1 1 1 1 1 1 1			for OPR-DIOS		(481)
										20.5	
1							1				
	NC-	POSITIONS S	AME AS	DIPFILE							
		POSITIONS S	7/17/85	1000							
							1				
- Mr. Call Call										1001	
2.5					1					\$18,500 to \$1500 MOVE	
									X	Asset State of the Control of the Co	
						1					
							-				
							0.00				
										CONTRACT TO THE	
6.											
TC.											
00	12 8 5 5									29004	
6	n	· · · · · · · · · · · · · · · · · · ·					15.000				
Annual Control of Control of Control							130000000000000000000000000000000000000				

	RESPONSIBLE	PERSONNEL	٠.٨.			
TYPE OF ACTION	NA	ME	ORIGINATOR			
			PHOTO FIELD PARTY			
OR LEGTE INCRECTED ERON SEAWARD			HYDROGRAPHIC PARTY			
OBJECTS INSPECTED FROM SEAWARD			GEODETIC PARTY			
			OTHER (Specify)			
F-OSITIONS DETERMINED AND/OR VERIFIED			FIELD ACTIVITY REPRESENTATIVE			
FOSTITORS BETERMINES KIND, ON TERMINES			OFFICE ACTIVITY REPRESENTATIVE			
FORMS ORIGINATED BY QUALITY CONTROL	/		REVIEWER			
AND REVIEW GROUP AND FINAL REVIEW	M.B. Hickson	2	QUALITY CONTROL AND REVIEW GROUP			
ACTIVITIES			REPRESENTATIVE			
	INSTRUCTIONS FOR ENTRIES UNDER					
	(Consult Photogramme	etric Instructions No. 64,				
OFFICE		FIELD (Cont'd)				
I. OFFICE IDENTIFIED AND LO	_		eld positions** require			
Enter the number and dat		entry of method of location or verification,				
day, and year) of the ph		date of field work and number of the photo-				
identify and locate the	ubject.	graph used to locate or identify the object.				
EXAMPLE: 75E(C)6042 8-12-75		EXAMPLE: P-8-V				
		8-12-75				
		74L (C) 2982				
FIELD	OD WED15150	II TOLANGULATION STATIO	N DECOVEDED			
I. NEW POSITION DETERMINED		II. TRIANGULATION STATION	id which is also a tri-			
	a by symbols as follows:	1				
	Photogrammetric	Rec. with date of re	s recovered, enter 'Triang.			
L - Located Vis V - Verified	- Visually	EXAMPLE: Triang. Rec	•			
	Field identified	8-12-75	•			
	Theodolite	0 12 /3				
	Planetable	ILL POSITION VERIFIED VI	SHALLY ON PHOTOGRAPH			
	Sextant	III. POSITION VERIFIED VISUALLY ON PHOTOGRAPH Enter 'V+Vis.' and date.				
4 - Resection 0 -	Sextant	EXAMPLE: V-Vis.				
A. Field positions* requ	ire entry of method of	8-12-75				
location and date of field work.						
EXAMPLE: F-2-6-L		AADUOTOODAMMETRIC EIELD POCITIONS and deconders				
8-12-75		**PHOTOGRAMMETRIC FIELD POSITIONS are dependent entirely, or in part, upon control established				
		by photogrammetric metho				
*FIELD POSITIONS are determined vations based entirely upon		by photogrammetric metho	ous.			

NOAA FORM 76-155 SURVEY NUMBER U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION (11-72)**GEOGRAPHIC NAMES** FE-233 WD BON PREVIOUS SURVEY OH CHART NO 49 CON U.S. MAPS ANGLE FROM FORMATION G RAPATLAS E OHLOCAL MAPS H U.S. LIGHT LIST Name on Survey 1 CAPE HENRY 2 CHESAPEAKE BAY 3 CRUMPS BANK 4 EAST OCERN VIEW 5 LITTLE CREEK 6 LITTLE CREEK 7 LYNNHAYEN ROADS 8 THIMBLE SHOAL CHANNEL VIRGINIA (title) 9 10 11 12 13 14 15 16 17 Approved: 18 19 20 Chief Geographer 21 22 1983 23 526 24 25

TOTALS 329 329 Pre-Verification by Beginning Date Ending Date Verification by Beginning Date Ending Date M.B.Hickson Apr. 19 19 1982 Jul. 1982 Verification Check by Date R.D.Sanocki 198 Jul Marine Center Inspection by Time (Hours) Hydrographic Inspection Team (AMC) 4 Jul. 198 Quality Control Inspection by Time (Hours) Date meletrere 198 Requirements Evaluation by Time (Hours)

5 Myers 3 ms 9-26-83

ATLANTIC MARINE CENTER VERIFICATION REPORT

REGISTRY NO.: FE-233 W.D.

FIELD NO.: R/H-20-2-69

Virginia, Chesapeake Bay, Off Little Creek and Cape Henry

SURVEYED: October 24 through November 26, 1969

SCALE: 1:20,000

PROJECT NO.: AMC-SP-5-69

SOUNDINGS: Wire Drag

CONTROL: Visual (Sextant Fixes

on Shore Signals)

. J. Morley

Smooth Sheet by M. B. Hickson

PURPOSE OF SURVEY

The purpose of this survey was to investigate and prove or disprove the existence of two items in the Chesapeake Bay off Little Creek and Cape Henry. The results of the investigations are discussed in this report and are portrayed on the smooth sheets (A&D) included in the Descriptive Report. The investigation of item 2 is incomplete. See H. 9255WD (1971-72) for resolution of the chief dangerous subm. wk in lat. 36°57.30'W, long. 76°04.05'W. (Hem 2)

2. CONTROL AND SHORELINE

- Attachment I of the Descriptive Report. Section 6.b. of this report addresses this deficiency. Control 1s not plotted on the AFD sheets but 1s shown on an overlay filed with the survey records.
- b. Shoreline portrayed on the smooth sheets (A&D) is intended for orientation purposes. The source of shoreline is from Chart 481, 17th edition, July 19, 1969.

3. JUNCTIONS

The present field examination junctions with subsequent survey H-9255 W.D. (R/H-20-1-71 and R/H-20-2-72) which has not been completely processed. Upon completion of H-9255 W.D. a junction will be effected with this field examination.

4. COMPARISON WITH HYDROGRAPHIC SURVEYS

a. Hydrography

H-9814 (1980) 1:10,000 H-9910 (1980) 1:10,000 Comparison with prior hydrographic surveys was not accomplished for this survey. Comparisons of prior data within the common area will be discussed in the Verification Reports of Surveys H-9814 (1980) and H-9910 (1980).

Subsequent hydrographic Surveys H-9814 (1980) and H-9910 (1980) cover 100% of this wire drag survey. Detailed comparisons between these hydrographic surveys and this wire drag survey will be accomplished in the Verification Reports of the above hydrographic surveys.

b. Wire Drag Surveys

H-9255 W.D. (1971-72) FE-154 W.D. (FE No. 13, 1957) H-7177 W.D. (1947-48) H-7028 W.D. (1945)

- 1) H-9255 W.D. (1971-72) is a subsequent wire drag survey common VR. item #3 to the present survey areas and has not been completely processed as of this date. a junction will be Comparisons with the present survey are deferred until the processing of H-9255 effected upon is completion of H-9255 processing of H-925
- 2) FE-154 (F.E. No. 13, 1957) is common to the eastern portion of the area of investigation of item 2 on the present survey. The prior field examination did not cover the charted location of item 2. Within the common area of the present and prior field examinations the present survey obtained effective depths from 5 feet deeper to 3 feet shoaler than the prior survey. No conflicts exist between present and prior effective depths within the common area. **concur**
- 3) H-7177 W.D. (1947-48) is common to the western half of the area of investigation of item 2 and a very small area in the northwestern portion of the area of investigation of item I on the present survey. Within the common area of item I, no hangs were encountered by either the present or prior survey. The present survey has effective depths from 5 to 6 feet deeper than the prior survey within the common area of item I. The present survey hung an obstruction at Latitude 34 ft hang, not 36 57.74; Longitude 76 05.30 but neither investigated nor cleared this hang. The cleared-cleared hydrographer identified this hang as a wreck hung on a previous wire drag survey by 36 ft on H-925; This prior survey shows a 35-foot sounding on an obstruction at Latitude 36°57.65°. Longitude 76°05.15' (280 meters southeast of the present hang) which the prior survey cleared by 32 feet. The present survey cleared the position of the prior 35-foot sounding by an effective depth of 34 feet in one direction only. As clearance is in one direction only on the present survey, it is recommended that the prior survey 35-foot sounding charted as an obstruction with a 32-foot clearance by wire drag remain as charted and that the uninvestigated hang located by the present survey be charted as a <u>dangerous submerged obstruction</u> in accordance with the results of the present survey. The prior survey located an old hulk at Latitude 36°57.55, entountered Longitude 76°04.54' with a hang depth of 34 feet, a sounding of 37 feet, and a clearance depth of 31 feet. The present survey did not hang this wreck but obtained a clearance depth of 35 feet in one direction only. This conflict is not considered significant as clearance on the present survey is in one direction only and the old hulk has possibly

settled in the 21 years between the prior and present survey. This wreck is charted #49255 wb as an obstruction with the 31-foot clearance by wire drag and since present clearance (1971-72) is in one direction only, it is recommended that the 31-foot clearance by wire drag also cleaned be retained with the wreck notation. Both the obstruction and the old hulk located this wreck by the prior survey have been brought forward to the present survey. The prior survey with 35 ft covers the area where two other hangs were encountered on the present survey but in the same by an effective depth considerably shoaler than the clearance depths obtained on direction. These hangs by the present survey. The present survey has effective depths from Recommend I to 9 feet deeper than the prior survey within the common area of item 2. No charting 35 with conflicts exist between present and prior effective depths within the common area except the previously mentioned hang on the old hulk at 34 feet. do not concur

4) H-7028 W.D. (1945) is common to a small area in the eastern portion of the area of investigation of item 2 on the present survey. The prior survey did not cover the charted location of item 2. The present survey did clear a prior uncleared grounding at Latitude 36°56.70', Longitude 76°02.08' of 43½ feet by a clearance depth of 38 feet in one direction. This grounding is charted as a 43-foot sounding and it is recommended to retain this sounding as charted. This grounding has been brought forward to the present survey. The present survey has effective depths from 3 to 15 feet shoaler than the prior survey within the common area. No conflicts exist between present and prior effective depths within the common area.

5. COMPARISON WITH CHART 481, 17th Edition, July 19, 1969

a. Hydrography

Charted hydrography within the common area originates with prior surveys H-7750 (1948-50), H-7721 (1949), H-7090 (1946), H-7089 (1946), H-7024 (1944-45), and H-6962 (1944) and soundings from sources not readily ascertainable. The disposition of the charted hydrography in the common area to this wire drag field examination will be discussed in the Verification Reports of H-9814 (1980) and H-9910 (1980).

Charted wire drag data within the common area originates with prior surveys H-7177 W.D. (1947-48) and H-7028 W.D. (1945) which are adequately discussed in section 4 of this report. Additional charting recommendations based on the results of this present field examination are as follows:

I) Item I - is identified as an <u>obstruction</u>; charted at Latitude 36°55.80', Do not concur Longitude 76°09.56'; a 3 ft. by 3 ft. concrete block, source unknown. The present expunge this represurely did not locate the concrete block, however an unidentified hang listed as orted obstruction below is approximately 95 meters east of the charted obstruction. A clearance a dangerous submit depth of 14 feet was obtained over the reported position. As clearance depths throughout in item a 1/2 mile radius of search are not within 3 feet of the bottom, the item is not disproved. 5.a.1) e on It is recommended that this item be retained as charted. Seven hangs and one grounding page 4 of were encountered during the investigation on item 1. The hangs and grounding are

a) Obstruction - cargo lost during transfer between Navy ships, hung at an effective depth of 22 feet at Latitude 36°56.52', Longitude 76°09.98' and cleared (in only one direction) by an effective depth of 21 feet. It is recommended that this item be charted as a dangerous submerged obstruction in accordance with the results of the present survey.

- b) Temporary hang on Fish Net hung at an effective depth of 15 feet at Latitude 36°55.88', Longitude 76°10.14' and cleared by an effective depth of 14 feet. It is recommended that this hang not be charted as a fish net hung in 1969 is not presently considered a hazard to navigation and additionally the hang is outside the anchorage area and in close proximity to the shore.
- c) Uninvestigated hang, possible hang on bottom hung at an effective depth of 16 feet (estimated) at Latitude 36°55.90', Longitude 76°10.07' and cleared by an effective depth of 15 feet. As charted depths in the area of the hang are 16 to 18 feet and subsequent survey H-9910 (1980) depths are 18 feet, it is recommended that this hang not be charted as it is outside the anchorage area, in close proximity to the shore, claimed as due to a mis-set upright by the hydrographer, and displays the characteristics of a bottom hang. Do not chart
- d) Debris, 150 feet of wire cable recovered off the bottom-hung Do not concur. at an effective depth of 16 feet (estimated) at Latitude 36°55.88', Longitude 76°09.59'The wire cable and cleared by an effective depth of 15 feet. It is recommended that this item belong wire and charted as a dangerous submerged obstruction in accordance with the results of the was removed present survey.
- e) Uninvestigated hang, possible hang on bottom hung at an Concur, this may be effective depth of 15 feet at Latitude 36°55.81', Longitude 76°09.48' and cleared the 3k3' concrete by an effective depth of 14 feet. Due to the close proximity to the charted position as a dangerous of item 1, it is recommended that this item be charted as a dangerous submerged subm. obstr., reprobstruction in accordance with the results of the present survey. See Item 5.a.1) on pg.3 of the V.R.

f) Rock - hung at an effective depth of 19 feet (estimated) at Do not concur.

Latitude 36°55.95', Longitude 76°09.06' and cleared by an effective depth of 19 feet. Diver held au.

It is recommended that this item be charted as a dangerous submerged obstruction legaline on this in accordance with the results of the present survey. Chart as 220bst depth of 22ft was obtained, see also 0.R.

- g) Uninvestigated temporary hang hung at an effective pg.5, 1tem k.2.

 depth of 19 feet at Latitude 36°55.86', Longitude 76°08.74' and cleared by an effective depth of 18 feet. It is recommended that this item be charted as a dangerous submerged obstruction in accordance with the results of the present survey. concur
 - h) Grounding grounding of drag at an effective depth of 22 feet at approximately Latitude 36°56.17', Longitude 76°09.90' and cleared by an effective depth of 21 feet. Charted depths in this area are 25 feet and subsequent survey H-9910 (1980) depths in the area are 27 feet. Although this grounding indicates a shoaler bottom than charted, it is recommended that the grounding not be charted as subsequent survey H-9910 (1980) shows no evidence of shoaling in the area and there is the possibility of an upright slippage in the grounded sections. Concur
 - 2) Item 2 is identified as a <u>wreck, PD</u>; charted at Latitude 36°57.30', This item was Longitude 76°04.05'; submerged wreck of the fishing vessel MINNIE V; source unknown. 49255 wD The present survey did not locate the item but obtained a clearance depth of 36 (1971-72). See feet over the reported position. As the clearance depths are not within three feet 49255 for a of the bottom and the area of investigation is not complete, the wreck is not disproved. The second triangly lt is recommended that this item be retained as charted. Three hangs were encountered during the investigation on item 2. These hangs are as follows:

* Disregard this recommendation. Chart a subm. obstracleared by 17 ft as shown on H.9255 wD (1971-72)

a) 4 Uninvestigated hang - hung at an effective depth of 34 feet See also D.R. at Latitude 36°57.73', Longitude 76°05.30' and not cleared. This hang was claimed pg 3.#65 ViR. by the hydrographer to be a wreck hung on a prior wire drag survey, however there are no indications or documents to support this claim. It is recommended that this hang be charted as a dangerous submerged obstruction in accordance with the results Aword of the present survey.

b) Uninvestigated hang, possible hang on bottom - hung at an effective depth of 38 feet at Latitude 36°57.06', Longitude 76°03.70' and cleared (in only one direction) by an effective depth of 35 feet. As charted depths in the area are 40 to 41 feet and subsequent survey H-9814 (1980) depths in the area are 40 to 41 feet, it is recommended that this hang not be charted since the hang displays the characteristics of a bottom hang. (Ground ing)

c) Uninvestigated temporary hang - hung at an effective depth chart 38 obst of 38 feet at Latitude 36 57.17, Longitude 76 03.30' and cleared by an effective depth of 38 feet. It is recommended that this hang be charted as a non dangerous submerged obstruction since it protrudes less than 3 feet above the bottom as charted depths and subsequent survey H-9814 (1980) depths are 40 to 41 feet in the area.

b. Aids to Navigation

No floating aids to navigation were located by the present survey.

Three fixed aids to navigation were used as control stations and are plotted on the lay is filed accompanying horizontal control overlay. The three fixed aids to navigation are with the survey Cape Henry Light (CAPE HENRY LIGHTHOUSE, 1887) and Little Creek Harbor records

Jetty Light I (LITTLE CREEK, 1929) which are published triangulation stations and Thimble Shoal Tunnel South Light which is a private maintained aid published in the Fixed and Floating Aids to Navigation List for OPR-D103. These three fixed aids to navigation are listed in the survey control list.

6. CONDITION OF SURVEY

The condition of the survey is satisfactory except as follows:

a. Field Work and Records

- 1) The entire survey was conducted using local time (075° W. Meridian) instead of Universal Coordinated Time (0° Meridian).
- 2) The investigation of item 2 is not complete. Only approximately 25% of the one mile radius area of search was covered. ✓
- 3) In the area covered in the item 2 investigation, effective depths ranged from 1 to 18 feet above the bottom. Generally effective depths are not within 3 feet of the bottom.
- 4) In the area covered in the item I investigation, effective depths ranged generally from 0 to 6 feet above the bottom. Bottom coverage in this area is good considering the methods and equipment used and the configuration of the bottom in this area.

- 5) No areas of splits and no areas of insufficient overlap exist in the survey.
- 6) Eight out of the ten hangs encountered on this survey were not investigated. Two hangs were identified only by retrieving material snagged on the ground wire, the other six hangs remain unidentified.
- 7) Nine of the 19 survey strips were not field plotted in regard to subdivision for effective depth and drag bights and hangs. Not all strips were used to compile the field A&D sheets. <
- 8) Four strips had uprights set in such a manner as to have one or more deeper sections between two inclined sections leading to lesser depths, which is in conflict with the requirements of section 3-20 of the Wire Drag Manual. In all cases the deeper sections were considered as being set to the depth of the shoaler adjacent sections during processing.
 - 9) No drag journals were written for any of the survey strips.
- 10) More frequent lift tests would have been desirable. Many strips had only one or two tests per section which is considered marginal for accurate determination of lift values.
- 11) No survey data was logged for entry into an automated system. All data required plotting by hand during processing.
 - 12) The hang at Latitude 36°57.73′, Longitude 76°05.30′ was not cleared. ✓
- 13) The hang at Latitude $36^{\circ}56.52$ ', Longitude $76^{\circ}09.98$ ' and the hang at Latitude $36^{\circ}57.06$ ', Longitude $76^{\circ}03.70$ ' were cleared in only one direction. \checkmark
- The least depth of 21.8 feet taken on the rock hung on strip L-1 Do not concur, was a reduced for predicted tides least depth. Neither the raw least depth nor the section is of value applied for predicted tides was stated in the survey records. At the time stated that all L.D. for the least depth the predicted tide curves show a -1½-foot predicted tide corrector sags were and the smooth tides show a -1½-foot actual tide corrector indicating that the reduced acquired least depth remains at 21.8 feet. However, since there is no information pertaining with alvers to acquisition (diver depth gage, lead line, echo sounder, or Bryson Gage), it is not considered as a useable least depth. This "rock", a clump of concrete, is described by the diver as lying in a depression and not projecting over the Descriptive Report surrounding bottom level. See section K, item #2 in the D.R.-Disregard this item, H-9255WD (1971-72) Information to the section of the level.
- 1) Prior surveys noted as source material for charted data were not identified nor were any comparisons made with the prior surveys.
- 2) Charts affected by this survey were not identified by edition number and edition data. Comparisons made by the hydrographer are inadequate and not in compliance with the <u>Wire Drag Manual.</u>
- 3) Attachment I of the Descriptive Report required the following revisions:

mation super

sedes this,

submobst.

clegred to

chart a

- a) Two control stations used for horizontal control were not listed. \checkmark
- b) No geographic positions of any of the control stations were listed in either the Descriptive Report or any of the survey records.
- c) The establishment dates listed for two control stations were in error. \checkmark
- d) Two control stations listed do not have any published geodetic data. Control station 009; Thimble Shoal Tunnel South Light, 1968; is on a published form 76-40 for OPR-D103 with an accuracy code claiming a third order position. Control station 010, R/H Hydrographic station, is claimed to be fourth order triangulation, however no records could be found for this station and therefore the geographic position was scaled from the boat sheet for incorporation into the survey records.
- 4) The List of Groundings and Shoals, section H, was not complete and was amended during verification. \checkmark
- 5) The Descriptive Report did not contain a Hydrographic Title Sheet (Form 77-28). This form was completed during verification and is included in the Descriptive Report.
- 6) A Geographic Names List (Form 76-155) was compiled during verification and is included in the Descriptive Report.
- 7) A Nonfloating Aids for Charts List (Form 76-40) was compiled during verification and is included in the Descriptive Report.
- 8) Necessary corrections made by the verifier to the Descriptive Report are denoted in red ink.

c. Field Plotting

Field plotting is satisfactory except as noted previously under the Field Work and Records portion of this section.

COMPLIANCE WITH PROJECT INSTRUCTIONS

This wire drag field examination adequately complies with Project Instructions AMC-SP-5-69, Little Creek, Virginia, dated October 8, 1969, except as noted in this report.

8. ADDITIONAL FIELD WORK

This is an adequate basic wire drag field examination except as noted in this report for item 2. Additional field work is recommended for item 2. (Item 2 was reassigned and reinvestigated on H-9255 W.D. both in the 1971 and 1972 portions as item 13.) Item 2 15 the wreck of the fishing vessel Minnie II, charted as a dangerous subm wk PP, from a miscellaneous source in 191.36°57.30′N, long 76°0405′W (charted depths 39 to 40 ft) cleared to 36 ft. See H-9255WD (1971-72) for a charting recommendation.

9. MISCELLANEOUS

- a. Four temporary hangs were encountered during this survey. These temporary hangs are positioned by using all available information pertaining to the hang, however the position is not as accurate as solid hang where numerous cuts for hang positioning are taken.
- b. Numerous groundings occurred during this survey, however only groundings that show conflict are smooth plotted. One grounding is smooth plotted, see section 5. of this report for discussions and recommendations.
- c. Hangs in void sections were smooth plotted with an estimated effective depth of hang. Four hangs on this survey have estimated effective depths. \checkmark
- d. In strips containing a hang the area past the initial contact of the hang was not claimed for effective depth coverage as the program of testing for lift is not considered sufficient to claim effective depths past the point of hang. \checkmark

Marsie B. Hickon, W.

Maurice B. Hickson, III Cartographer Evaluation and Analysis

INSPECTION REPORT FE-233WD

The completed survey has been inspected by the Hydrographic Inspection Team with regard to survey coverage, investigation of hangs and clearance depths, cartographic symbolization, and verification or disproval of charted data. The Verification Report has presented the facts accurately and properly, the procedures used were appropriate, and the recommendations are logical and justifiable. The survey complies with National Ocean Survey requirements except as noted in the Verification Report. The survey records comply with NOS requirements except where noted in the Verification Report. The Hydrographic Inspection Team concurs with the verifier's findings, actions, and recommendations.

> Examined and Approved Hydrographic Inspection Team

Kieninger, &DR, NOAA

Chief, Processing Division

Field Procedures Officer

Operations Division

Chief, EDP Branch Processing Division

Approved/Forwarded July 12, 1982

Houlder, RADM, NOAA Director, Atlantic Marine Center



UNITED STATES DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

NATIONAL OCEAN SERVICE
OFFICE OF CHARTING AND GEODETIC SERVICES
ROCKVILLE, MARYLAND 20852

N/CG242:FPS

May 13, 1985

T0:

Roy K. Matsushige axm

Chief, Hydrographic Surveys Branch

THRU:

Chief, Standards Section

FROM:

F. P. Saulsbury 0.0

Quality Evaluator

SUBJECT:

Quality Control Report for Survey FE-233 WD (1969), Virginia,

Chesapeake Bay, Off Little Creek and Cape Henry

A quality control inspection of FE-233 WD was accomplished to monitor the survey for adequacy with respect to data acquisition; determination of the validity of hangs, groundings, and least depths; validity of cleared depths over obstructions in the survey area; A&D sheets; Verifier's Report; decisions and actions by the verifier; and the cartographic presentation of data. In general, it was found to conform to National Ocean Service standards and requirements except as stated in the Descriptive Report.

Additional notes were appended to Descriptive Report items during quality control inspection.

cc: N/CG241


NOTE:


6/25/85


BECAUSE THE PROJECT INSTRUCTIONS
FOR THIS SURVEY CANNOT BE FOUND,
NO REPORT OF COMPLIANCE WILL
BE WRITTEN.


N/CG Z4x1














NAUTICAL CHART DIVISION

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. FE-233 W.D.

INSTRUCTIONS

- A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

Letter all information.
 In "Remarks" column cross out words that do not apply.
 Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review

CHART	DATE	CARTOGRAPHER	REMARKS
12254	2-20-86	Pusself PKerneds	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 55
12296	3-2486	JEP. ALIENO	Full Part Before After Verification Review Inspection Signed Via
		0	Drawing No. 52 Applied through 12254
12222	7-10-86	Russell PKennely	Full Part Before After Verification Review Inspection Signed Via
		8	Drawing No. 3
10001	0.05	0.11	
12221	9-25-86	Russell & Kennesh	Full Part Before After Verification Review Inspection Signed Via
		O.	Drawing No. 83 Applied through 12222 312254
2256	01-08-85	Desce A Johnson	Full Part Before After Verification Review Inspection Signed Via
		Applied Thu	Drawing No.
		cht. 12254	
12205	10-6-87	g. Bail	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. 20 App'd. thrn 12221 #83
12208	11/5/2	- 	
12200	11/19/91	J. ROBINSON	Full Part Before After Verification Review Inspection Signed Via
			Drawing No. // Reconstruction
		,	Applied though 1222
			Full Part Before After Verification Review Inspection Signe: Vi
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			Full Part Before After Verification Review Inspection Signed Via
			Drawing No.
			SANDAD CKD 7-17-85
			$C\omega_{I}$
_			
			526